

**PREFINISHED WIDE PLANK BAMBOO FLOORING**

**Teragren® Craftsman II**

**FloorScore®-certified; FSC-Pure by special order**



**MF '04 SECTION 09640**

DOC: CRFTII 7.28.11

LEED® MR6, IEQ 4.3

\*\*\*\*\*

NOTES TO SPECIFIER:

THIS SPECIFICATION SECTION HAS BEEN PREPARED TO ASSIST DESIGN PROFESSIONALS IN THE PREPARATION OF PROJECT OR OFFICE MASTER SPECIFICATIONS. IT FOLLOWS GUIDELINES ESTABLISHED BY THE CONSTRUCTION SPECIFICATIONS INSTITUTE, AND THEREFORE MAY BE USED WITH MOST MASTER SPECIFICATION SYSTEMS WITH MINOR EDITING.

EDIT CAREFULLY TO SUIT PROJECT REQUIREMENTS. MODIFY AS NECESSARY AND DELETE ITEMS THAT ARE NOT APPLICABLE. VERIFY THAT REFERENCED SECTION NUMBERS AND TITLES ARE CORRECT. (NUMBERS AND TITLES REFERENCED ARE BASED ON *MASTER FORMAT*, 2004 EDITION)

THIS SECTION ASSUMES THE PROJECT MANUAL WILL CONTAIN COMPLETE DIVISION 1 DOCUMENTS INCLUDING SECTIONS 013300 – SUBMITTAL PROCEDURES, 016000 –PRODUCT REQUIREMENTS, 017700 –CLOSEOUT PROCEDURES. CLOSE COORDINATION WITH DIVISION 1 SECTIONS IS REQUIRED. IF THE PROJECT MANUAL DOES NOT CONTAIN THESE SECTIONS, ADDITIONAL INFORMATION SHOULD BE INCLUDED UNDER THE APPROPRIATE ARTICLES.

\*\*\*\*\*

**PART 1 - GENERAL**

**1.01 SUMMARY**

- A. Section Includes: Prefinished wide plank bamboo flooring and matching accessories installed by the [nail or staple down method.] [floating floor method.] [glue down method.] [nail or staple and glue-down method.]

\*\*\*\*\*

INCLUDE SECTION NUMBER AND TITLE BELOW FOR OTHER TYPES OF FLOORING MATERIALS BORDERING THE BAMBOO FLOORING, AND FINISHED TRIM SUCH AS BASEBOARDS IF NOT INCLUDED IN THIS SECTION.

\*\*\*\*\*

- B. Work in other sections:
  - 1. For project sustainability requirements, See 018113 “Sustainable Design Requirements”

**1.02 SUBMITTALS**

- A. Submit the following items:
  - 1. Product Data:
    - a. Flooring Specification Sheet.
    - b. Finish data: finish type, composition and manufacturer (See summary in section 2.02).
    - c. Proof of supplier’s legal right to provide product

Teragren CRAFTSMAN II Wide Plank Bamboo Flooring  
Teragren LLC

Disclaimer: Teragren LLC has provided this information “as is” without warranties of any kind, expressed or implied. Teragren LLC has made every reasonable effort to ensure the accuracy of the information provided in this document but we are not responsible for typographical errors and omissions.

- d. Material Safety Data Sheet (MSDS) (submit if required for LEED submittal)
  - e. [FloorScore®](#) certification #SCS-FS-01878: Air quality certification from Resilient Floor Covering Institute - [www.rfci.com](http://www.rfci.com)
  - f. Certified Hardness Tests, Janka results (See summary in section 2.02).
  - g. Manufacturer's installation guidelines and installation requirements.
  - h. ISO-9001 and 14001 factory certifications.
  - i. Forest Stewardship Council Chain-of-Custody #SCS-COC-002912 (special order product; submit if required for LEED submittal)
- 2. Accessory profiles (See specification in section 2.03).
  - 3. Installation adhesive.

\*\*\*\*\*  
**NOTE:** IF INSTALLATION IS "GLUE DOWN" REQUEST A SUBMITTAL ON THE INSTALLATION ADHESIVE.  
 \*\*\*\*\*

- 4. Warranty for Architect's review.
  - 5. Shop Drawings: Include direction of flooring, fastening method to be used, patterns and transition accessories. Include large scale details of accessories and details of all transitions. Make shop drawings in module required by Architect or electronically using Architects' format.
  - 6. Samples:
    - a. Minimum 3.875 inches (98.42 mm) long strip of flooring plank, with manufacturer identified.
    - b. Fasteners.
    - c. One of each specified accessory, minimum 3.875 inches (98.42 mm) long.
  - 7. Quality Assurance/Control Submittals:
    - a. Test Report: Electronic copy of lab reports including name and contact information of certified lab.
    - b. Manufacturer's Installation Guidelines
- B. Closeout Submittals, submit following items:
    - 1. Maintenance instructions
    - 2. Special Warranties for use in Owner's manual.

### 1.03 QUALITY ASSURANCE

- A. Qualifications:
  - 1. Manufacturer Qualifications:
    - a. Minimum 20 years' experience in manufacturing and distributing bamboo flooring.
  - 2. Installer Qualifications:
    - a. Minimum three years experience in bamboo / hardwood flooring installation.
    - b. Minimum three years experience in installation of bamboo / hardwood flooring over radiant heating systems. (use only if necessary)
- B. Pre-Installation Meeting:
  - 1. Convene meeting at project site within one week of scheduled start of installation with representatives of the following in attendance: Architect, General Contractor, and Sub-Contractor.
  - 2. Review project / site conditions, requirements of related work, requirements for operation of HVAC system, installation guidelines, storage and handling procedures, and protection measures.
  - 3. Discuss responsibilities of various parties and deviations from specifications and guidelines for installation.
  - 4. Distribute minutes to attendees within 48 hours.

### 1.04 DELIVERY, STORAGE, AND HANDLING

- A. Deliver flooring to project site in original boxes not less than 5 days prior to start of installation. Allow sufficient time for flooring to acclimate to site conditions.
- B. Store flooring materials in conditioned space at all times, and do not allow to freeze or get wet.

Teragren CRAFTSMAN II Wide Plank Bamboo Flooring  
 Teragren LLC

Disclaimer: Teragren LLC has provided this information "as is" without warranties of any kind, expressed or implied. Teragren LLC has made every reasonable effort to ensure the accuracy of the information provided in this document but we are not responsible for typographical errors and omissions.

1.05 PROJECT/SITE CONDITIONS

\*\*\*\*\*  
**RADIANT HEAT NOTE:** SELECT "5 DAYS" IN FOLLOWING PARAGRAPH IF FLOORING IS TO BE INSTALLED OVER A RADIANT HEAT SYSTEM; OTHERWISE, SELECT "72 HOURS."  
\*\*\*\*\*

- A. Environmental Requirements: All installation spaces, flooring and adhesive must be maintained at normal occupancy temperature and humidity levels for a minimum of [72 hours] [5 days] prior to and continuously following installation. HVAC systems must be operational and controlling site temperature and humidity.

1.06 WARRANTY

- A. Warranty for Prefinished Teragren Craftsman II Bamboo Flooring:
  - 1. Teragren Structural Warranty: Lifetime against de-lamination, separation, buckling or cupping as a result of a manufacturing defect. Please see [www.teragren.com](http://www.teragren.com) for current product warranty.
  - 2. Teragren Commercial Finish Warranty: 10 years against wear through to the underlying flooring or separation from the flooring as a result of a manufacturing defect. Please see [www.teragren.com](http://www.teragren.com) for current product warranty.

\*\*\*\*\*  
USE ABOVE FINISH WARRANTY FOR COMMERCIAL PROJECTS. USE FOLLOWING FINISH WARRANTY FOR RESIDENTIAL PROJECTS.  
\*\*\*\*\*

- 3. Teragren Residential Finish Warranty: 25 years against wear through to the underlying flooring or separation from the flooring as a result of a manufacturing defect. Please see [www.teragren.com](http://www.teragren.com) for current product warranty.

PART 2 - PRODUCTS

2.01 MANUFACTURER

- A. Teragren LLC  
12715 Miller Road NE, Suite 301  
Bainbridge Island, WA 98110  
Tel: (800) 929-6333  
Fax: (206) 842-9456  
e-mail: [info@teragren.com](mailto:info@teragren.com)  
Website: <http://www.teragren.com>

\*\*\*\*\*  
INSERT NAME, ADDRESS AND PHONE NUMBERS OF LOCAL DISTRIBUTOR/DEALER BELOW.  
\*\*\*\*\*

- 1. Distributor/Dealer:

B. Craftsman II Bamboo Flooring – Solid Bamboo:

- 1. Vertical Grain: Bamboo strips laminated together with edges exposed to the wear surface to form a solid bamboo plank without internal voids.
  - a. Color: [Natural] [Caramelized].
- 2. Flat Grain: Bamboo strips laminated together face up to form a 3-ply solid bamboo plank without internal voids.
  - a. Color: [Natural] [Caramelized].



- C. Note: FSC-Pure certified bamboo by special order.
- D. Note: Formaldehyde-free manufacturing adhesive by special order.
- E. Substitutions: None Permitted.

Teragren CRAFTSMAN II Wide Plank Bamboo Flooring  
Teragren LLC

Disclaimer: Teragren LLC has provided this information "as is" without warranties of any kind, expressed or implied. Teragren LLC has made every reasonable effort to ensure the accuracy of the information provided in this document but we are not responsible for typographical errors and omissions.

2.02 MATERIALS

A. Bamboo Flooring:

1. Species: Moso (Phyllostachys Pubescens).
2. Bamboo Harvest: Bamboo harvested between 5-1/2 to 6 years to ensure color clarity, hardness and stability of fiber.
3. Two Stage Moisture Balancing Process: Raw materials and finished product are moisture balanced to equilibrium at 45-50% Relative Humidity
4. Size: (nominal) 5.5 inches wide by 5/8 inch thick by 75.5 inch lengths (exact) 1920x138x15mm.
5. Edge: Tongue and groove with micro-bevel edge.
6. Back: Channeled.
7. Chemical Treatment: Natural borate solution and hydrogen peroxide to eliminate pests and mildew at time of manufacture. Note: Treatment is only applied to Flat Natural (FGN) and Vertical Natural (VGN) traditional bamboo.
8. Finish: Seven-coat, 100 percent solids, non off-gassing, water-based system with aluminum oxide with two top coats of scratch-resistant polyurethane.
9. Physical Property Performance Requirements:
  - a. Hardness: ASTM D 1037, Janka Ball: Minimum 1984 Flat Natural, 1950 Vertical Natural, 1825 Flat Caramelized, 1747 Vertical Caramelized.
  - b. Dimensional Stability: ASTM D 1037: Dimensional change coefficient: 0.0004 parallel / 0.0027 perpendicular / 0.003 thickness.
  - c. Abrasion Resistance: ASTM D 4060, CS-17 Taber abrasive wheels: Final wear-through: Minimum 27,500 cycles.
  - d. Slip Resistance: ASTM D2394, Coefficient of Friction Average; Static 0.592; Sliding 0.62.
  - e. Moisture Content: ASTM D 4442, Oven Dry Method: 6-8 percent average.
  - f. Formaldehyde Emissions: ASTM E 1333: Maximum 0.021 ppm average.
  - g. ASTM C 518-04: R value of 0.6.

B. Installation Adhesive: One-part water-free premium urethane wood floor adhesive or equivalent.

C. Nails or Staples:

1. 1-1/2 Inch Thick Subfloor: 2 inch nails or staples.
2. 3/4 Inch Thick Subfloor: 1-1/2 inch nails or staples.
3. 1 inch Thick Plywood Subfloor over concrete: 1-1/4 inch nails or staples.

2.03 ACCESSORIES

- A. Stair Treads: 11-1/2 inches (292.1 mm) wide by 1-1/16 inches (26.98 mm) thick in both 48 inch (1219.2 mm) and 96 inch (2438.4 mm) lengths [\_\_\_\_\_ inches ( \_\_\_\_\_ mm) wide by \_\_\_\_\_ inches ( \_\_\_\_\_ mm) thick by [\_\_\_\_\_ inches ( \_\_\_\_\_ mm) long]. Match flooring grain, color, and finish.
- B. Stair Riser: 7-1/2 inches (190.5 mm) wide by 5/8 inch (15.87 mm) thick in both 48 inch (1219.2 mm) and 96 inch (2438.4 mm) lengths [\_\_\_\_\_ inches ( \_\_\_\_\_ mm) wide by \_\_\_\_\_ inches ( \_\_\_\_\_ mm) thick by [\_\_\_\_\_ inches ( \_\_\_\_\_ mm) long]. Match flooring grain, color, and finish.
- C. Stair Nosing: [3-1/2 inches (88.9 mm) wide by 1-1/8 inches (28.575 mm) thick] [ \_\_\_\_\_ inches ( \_\_\_\_\_ mm) wide by \_\_\_\_\_ inches ( \_\_\_\_\_ mm) thick]. Match flooring grain, color, and finish.

\*\*\*\*\*  
 IF TRANSITION STRIPS TO OTHER FLOORING MATERIALS ARE REQUIRED, VERIFY WHICH FLOORING INSTALLER SHOULD PROVIDE THE TRANSITIONS AND INCLUDE BELOW OR IN ANOTHER SECTION AS APPROPRIATE.  
 \*\*\*\*\*

- D. Floating Stair Nosing: 4-1/8 inches (104.77 mm) wide by 1-3/8 inches (34.92 mm) thick [\_\_\_\_\_ inches ( \_\_\_\_\_ mm) wide by \_\_\_\_\_ inches ( \_\_\_\_\_ mm) thick]. Match flooring grain, color, and finish.

Teragren CRAFTSMAN II Wide Plank Bamboo Flooring  
 Teragren LLC

Disclaimer: Teragren LLC has provided this information "as is" without warranties of any kind, expressed or implied. Teragren LLC has made every reasonable effort to ensure the accuracy of the information provided in this document but we are not responsible for typographical errors and omissions.

- E. Clamshell Reducer Strip: [2-3/8 inches (60.235 mm) wide by 5/8 inch (15.875 mm) thick] [ \_\_\_\_\_ inches ( \_\_\_\_\_ mm) wide by \_\_\_\_\_ inches ( \_\_\_\_\_ mm) thick]. Match flooring grain, color, and finish.
- F. Floating Floor Reducer Strip: [2-1/2 inches (63.5 mm) wide by 13/16 inch (20.64 mm) thick] [ \_\_\_\_\_ inches ( \_\_\_\_\_ mm) wide by \_\_\_\_\_ inches ( \_\_\_\_\_ mm) thick]. Match flooring grain, color, and finish.
- G. T-Mold: [2 inches (50.8 mm) wide by 15/16 inch (23.81 mm) thick] [ \_\_\_\_\_ inches ( \_\_\_\_\_ mm) wide]. Match flooring grain, color, and finish.
- H. Base Shoe: [3/4 inch (19.05 mm) high by 1/2 inch (12.7 mm) thick] [ \_\_\_\_\_ inches ( \_\_\_\_\_ mm) wide by \_\_\_\_\_ inches ( \_\_\_\_\_ mm) thick]. Match flooring grain, color, and finish.
- I. Base Molding: [3-1/2 inches (88.9 mm) high by 1/2 inch (12.7 mm) thick] [ \_\_\_\_\_ inches ( \_\_\_\_\_ mm) wide by \_\_\_\_\_ inches ( \_\_\_\_\_ mm) thick]. Match flooring grain, color, and finish.
- J. Baby Threshold: [2 inches (50.8 mm) wide by 1 inch (25.4 mm) thick] [ \_\_\_\_\_ inches ( \_\_\_\_\_ mm) wide by \_\_\_\_\_ inches ( \_\_\_\_\_ mm) thick]. Match flooring grain, color, and finish.
- K. Architectural Molding: [2 inch (50.8mm) & 3-5/8 inch wide by 3/4 inch (19.05 mm) thick] [ \_\_\_\_\_ inches ( \_\_\_\_\_ mm) wide by \_\_\_\_\_ inches ( \_\_\_\_\_ mm) thick]. Match flooring grain, color, and finish.

\*\*\*\*\*  
 FLOOR VENTS ARE AVAILABLE IN SEVERAL STANDARD SIZES AND CUSTOM SIZES. VERIFY THAT APPROPRIATE VENTS ARE NOTED ON THE DRAWINGS .  
 \*\*\*\*\*

L.. Floor Vent: Size and type as shown on Drawings. Match flooring grain, color, and finish.

\*\*\*\*\*  
 INCLUDE ADDITIONAL ACCESSORIES SUCH AS METAL OR WOOD FEATURE STRIPS IF USED IN THE PROJECT.  
 \*\*\*\*\*

PART 3 - EXECUTION

3.01 EXAMINATION

- A. Examine substrates upon which flooring will be installed.
  - 1. Verify that subfloor is clean, dry, and free of contaminates or protruding fasteners.
  - 2. Test subfloor for moisture vapor emissions using a Calcium Chloride or equivalent test. Do not install flooring if vapor pressure exceeds 3 lbs per 1,000sf (15g per m<sup>2</sup>) within a 24 hour period.
    - a. In multiple story buildings, test each floor level scheduled to receive bamboo flooring.
    - b. Mark test location(s) on Record Drawings.

**Teragren strongly recommends the use of a moisture barrier underneath this product unless the subfloor can be guaranteed, in perpetuity, to not emit moisture vapor in excess of 3 lbs per 1,000sq. ft. (15g per m<sup>2</sup>) within a 24 hour period.**

- B. Verify that HVAC system is operating properly and maintaining proper occupancy level temperature and humidity conditions.
- C. Coordinate with responsible entity to correct unsatisfactory conditions.
- D. Commencement of work by installer is an acceptance of suitable substrate conditions.
- E. Prior to installation, the installer shall examine all material and determine that it matches the work order.

Teragren CRAFTSMAN II Wide Plank Bamboo Flooring  
 Teragren LLC

Disclaimer: Teragren LLC has provided this information "as is" without warranties of any kind, expressed or implied. Teragren LLC has made every reasonable effort to ensure the accuracy of the information provided in this document but we are not responsible for typographical errors and omissions.

3.02 PREPARATION

- A. Acclimatization: Open flooring boxes, remove shrink wrap and foam packing at a minimum of 3 days prior to start of installation.
- B. Grind and or fill subfloor using methods and materials appropriate to the subfloor construction to eliminate humps and depressions. For best results neither humps nor depressions shall exceed 1/8 of an inch (3 mm) within a 6 foot (1830 mm) radius or 3/16 of an inch (4.7 mm) within a 10ft (3048 mm) radius.
- C. Because bamboo is a natural fiber, variations in color naturally occur. Each box should be inspected for differences in color with color variance staggered throughout the floor.

3.03 INSTALLATION

\*\*\*\*\*  
 MANUFACTURER'S INSTALLATION GUIDELINES ARE ADEQUATE FOR NORMAL INSTALLATION CONDITIONS. UNUSUAL CONDITIONS MAY REQUIRE ADDITIONAL INFORMATION IN THIS ARTICLE.  
 \*\*\*\*\*

- A. Bamboo Flooring: Install in accordance with manufacturer's installation guidelines.
- B. Install flooring planks by [nail or staple down method.] [floating floor method.] [glue down method.] [nail or staple and glue-down method.]
- C. Lay flooring in the direction(s)/pattern(s) as shown on Drawings. Where not identified run plank length to match longest room dimension.
- D. Accessories: Install using methods appropriate to the accessory and flooring system.
- E. Accommodate thermal expansion. Install transitions, trims and base molding, as identified in manufacturer's installation guidelines and as required to accommodate site conditions.

3.04 CLEANING

- A. Remove all debris left from flooring installation; vacuum and leave flooring in clean, debris-free condition.

3.05 PROTECTION

- A. Cover installed flooring with heavy Kraft-paper or other suitable covering. Do not use a non-breathable sheet or film that could cause condensation to form. Maintain covering throughout remainder of construction period.

END OF SECTION<sup>1</sup>

---

<sup>1</sup> This specification was prepared by Teragren LLC. Comments or suggestions for improvement should be addressed to: Teragren, 12715 Miller Road NE, Suite 301, Bainbridge Island, WA 98110, 1-800-929-6333, [www.teragren.com](http://www.teragren.com) Email: [info@teragren.com](mailto:info@teragren.com)

Teragren CRAFTSMAN II Wide Plank Bamboo Flooring  
Teragren LLC

Disclaimer: Teragren LLC has provided this information "as is" without warranties of any kind, expressed or implied. Teragren LLC has made every reasonable effort to ensure the accuracy of the information provided in this document but we are not responsible for typographical errors and omissions.